



Strait Arrow

1006 Aversboro Rd, Garner, NC 27529
Phone: 919.609.2808 | Email: Straitarrow@yahoo.com

REPAIR & RECONSTRUCTION QUOTE

Insured: Hope Alfaro

Property: 1227 Seaton Road, Durham NC 27713

Date of Loss: 4/1/2026

Estimate #: 26-0843-REP

Date of Loss: 4/1/2026

Quote Date: May 4, 2026

Description	QTY	Unit	Unit Price	Total
MAIN LEVEL (GENERAL)				
Cleanup				
Haul debris - per pickup truck load incl. dump fees	1.00	EA	\$220.07	\$220.07
Final cleaning - construction - Residential	749.31	SF	\$0.47	\$350.67
LIVING ROOM				
Floor				
Vinyl plank flooring	376.10	SF	\$7.40	\$2,784.20
Quarter round - 3/4"	83.40	LF	\$2.52	\$209.83
Seal & paint base shoe / quarter round	83.40	LF	\$1.41	\$117.28
Walls				
Baseboard - 4 1/4"	83.40	LF	\$6.41	\$534.50
Paint baseboard - two coats	83.40	LF	\$2.53	\$210.68
Drywall patch / small repair, ready for paint	1.00	EA	\$138.06	\$138.06
Seal/prime (1 coat) then paint (1 coat) - patches	22.00	SF	\$1.65	\$36.39
Paint the walls - one coat	656.20	SF	\$1.17	\$767.75
FOYER				
Floor				
Vinyl plank flooring	69.87	SF	\$7.40	\$517.23
Quarter round - 3/4"	33.91	LF	\$2.52	\$85.31
Seal & paint base shoe / quarter round	33.91	LF	\$1.41	\$47.69
Walls				
Baseboard - 4 1/4"	33.91	LF	\$6.41	\$217.35
Paint baseboard - two coats	33.91	LF	\$2.53	\$85.66
Seal/prime (1 coat) then paint (1 coat) - patches	100.00	SF	\$1.65	\$165.46
Paint the walls - one coat	285.11	SF	\$1.17	\$333.59
1/2" drywall - hung, taped, floated, ready for paint	81.00	SF	\$4.24	\$343.51
Corner bead - per LF	16.00	LF	\$10.11	\$161.75
Door jamb per LF - interior - paint grade 4 9/16"	18.00	LF	\$6.41	\$115.33
Casing - 2 1/4"	18.00	LF	\$3.41	\$61.30
Paint door/window trim & jamb - 2 coats per side	2.00	EA	\$55.42	\$110.84
Ceiling				
R&R Ductwork - flexible insulated 10" round	25.00	LF	\$19.52	\$488.01
1/2" drywall - hung, taped, floated, ready for paint	69.87	SF	\$4.24	\$296.32
Tape joint - new to existing drywall	47.34	LF	\$11.60	\$548.94

Description	QTY	Unit	Unit Price	Total
Light fixture - supply	1.00	EA	\$111.66	\$111.66
Light fixture - install	1.00	EA	\$69.08	\$69.08
Seal/prime (1 coat) then paint (1 coat) - ceiling	69.87	SF	\$1.65	\$115.59
LAUNDRY ROOM				
Floor				
Quarter round - 3/4"	11.31	LF	\$2.52	\$28.48
Seal & paint base shoe / quarter round	11.31	LF	\$1.41	\$15.90
Bifold pivot door hardware - detach & reset	2.00	EA	\$14.86	\$29.72
Walls				
Baseboard - 4 1/4"	11.31	LF	\$6.41	\$72.48
Paint baseboard - two coats	11.31	LF	\$2.53	\$28.57
Seal/prime (1 coat) then paint (1 coat) - walls	81.91	SF	\$1.65	\$135.52
1/2" drywall - hung, taped, floated, ready for paint	81.91	SF	\$4.24	\$347.37
Door jamb per LF - interior - paint grade 4 9/16"	18.00	LF	\$6.41	\$115.33
Casing - 2 1/4"	18.00	LF	\$3.41	\$61.30
Paint door/window trim & jamb - 2 coats per side	2.00	EA	\$55.42	\$110.84
Install bifold door set - Colonist Double	1.00	EA	\$149.18	\$149.18
Install shelving - wire vinyl coated	6.00	LF	\$9.34	\$56.02
Ceiling				
1/2" drywall - hung, taped, floated, ready for paint	12.23	SF	\$4.24	\$51.88
Tape joint - new to existing drywall	14.09	LF	\$11.60	\$163.40
Light fixture	1.00	EA	\$111.66	\$111.66
Seal/prime (1 coat) then paint (1 coat) - ceiling	12.23	SF	\$1.65	\$20.22
HALF BATHROOM				
Floor				
Vinyl plank flooring	22.91	SF	\$7.40	\$169.59
Quarter round - 3/4"	18.98	LF	\$2.52	\$47.75
Seal & paint base shoe / quarter round	18.98	LF	\$1.41	\$26.69
Toilet - reset	1.00	EA	\$217.99	\$217.99
Walls				
Baseboard - 4 1/4"	18.98	LF	\$6.41	\$121.65
Paint baseboard - two coats	18.98	LF	\$2.53	\$47.96
Seal/prime (1 coat) then paint (1 coat) - walls	154.27	SF	\$1.65	\$255.24
Paint the walls - one coat	154.27	SF	\$1.17	\$180.49
1/2" drywall - hung, taped, floated, ready for paint	154.27	SF	\$4.24	\$654.23
Interior door unit	1.00	EA	\$433.15	\$433.15
Detach & reset door knob - interior	1.00	EA	\$31.83	\$31.83
Paint door slab only - 2 coats per side	2.00	EA	\$66.70	\$133.40
Interior door - detach & reset - slab only	1.00	EA	\$29.84	\$29.84
Paint door/window trim & jamb - 2 coats per side	2.00	EA	\$55.42	\$110.84
Install light fixture	1.00	EA	\$69.08	\$69.08
Install vanity	3.00	LF	\$53.71	\$161.14
Install vanity top - one sink - cultured marble	3.00	LF	\$70.23	\$210.68
Plumbing fixture supply line	2.00	EA	\$29.62	\$59.24
P-trap assembly - ABS (plastic)	1.00	EA	\$89.51	\$89.51

Description	QTY	Unit	Unit Price	Total
Angle stop valve	2.00	EA	\$55.45	\$110.89
Ceiling				
1/2" drywall - hung, taped, floated, ready for paint	22.91	SF	\$4.24	\$97.15
Tape joint - new to existing drywall	20.98	LF	\$11.60	\$243.27
Heat/AC register - mechanically attached	2.00	EA	\$35.91	\$71.82
Seal/prime (1 coat) then paint (1 coat) - ceiling	22.91	SF	\$1.65	\$37.91
COAT CLOSET				
Floor				
Vinyl plank flooring	6.59	SF	\$7.40	\$48.77
Quarter round - 3/4"	7.97	LF	\$2.52	\$20.05
Seal & paint base shoe / quarter round	7.97	LF	\$1.41	\$11.23
Walls				
Baseboard - 4 1/4"	7.97	LF	\$6.41	\$51.09
Paint baseboard - two coats	7.97	LF	\$2.53	\$20.14
Paint the walls - one coat	67.49	SF	\$1.17	\$78.96
KITCHEN				
Floor				
Remove vinyl plank flooring	175.65	SF	\$1.93	\$339.36
Vinyl plank flooring	187.65	SF	\$7.40	\$1,389.14
R&R quarter round - 3/4"	63.63	LF	\$2.79	\$177.63
Seal & paint base shoe / quarter round	63.63	LF	\$1.41	\$89.49
Walls				
Mask and prep for paint - plastic/paper/tape per LF	70.65	LF	\$2.33	\$164.50
Paint baseboard - one coat	63.63	LF	\$1.67	\$106.11
Paint the walls - one coat	477.93	SF	\$1.17	\$559.18
Appliances				
Refrigerator - remove & reset	1.00	EA	\$64.29	\$64.29
Detach & reset range - slide-in electric	1.00	EA	\$48.21	\$48.21
Ceiling				
1/2" drywall - hung, taped, floated, ready for paint	12.00	SF	\$4.24	\$50.91
Tape joint - new to existing drywall	6.00	LF	\$11.60	\$69.58
Seal/prime (1 coat) then paint (1 coat) - patches	22.00	SF	\$1.65	\$36.39
Paint the ceiling - one coat	187.65	SF	\$1.17	\$219.53
Detach & reset ceiling fan & light	1.00	EA	\$311.56	\$311.56
MASTER BATHROOM				
Floor				
Tile floor covering	32.46	SF	\$18.69	\$606.56
1/2" cement board	32.46	SF	\$8.93	\$290.03
Underlayment - 1/4" 5 ply	32.46	SF	\$3.57	\$115.94
Caulking - acrylic	21.21	LF	\$4.12	\$87.40
Threshold - cultured marble	3.00	LF	\$60.15	\$180.46
Plumbing				
Angle stop valve	1.00	EA	\$55.45	\$55.45
Toilet flange	1.00	EA	\$367.53	\$367.53
Toilet - reset	1.00	EA	\$217.99	\$217.99

Description	QTY	Unit	Unit Price	Total
Plumbing fixture supply line	1.00	EA	\$29.62	\$29.62
Walls				
Install vanity	3.00	LF	\$53.71	\$161.14
Install vanity top - one sink - cultured marble	3.00	LF	\$70.23	\$210.68
Plumbing fixture supply line	2.00	EA	\$29.62	\$59.24
P-trap assembly - ABS (plastic)	1.00	EA	\$89.51	\$89.51

TOTAL	\$20,680.93
-------	-------------

Authorized Signature (Strait Arrow)

Date

Customer / Insured Signature

Date